Annual Index of Articles 1996

ADMIXTURES

Using Admixtures to Improve Chemical Resistance of Concrete: What admixtures can and can't do to reduce concrete permeability and improve its resistance to leaching, sulfates, and acids. **(3 pp; 96:541)**

New Admixture Combats Concrete Shrinkage: A new liquid admixture allows contractors and ready mix producers to reduce shrinkage without adding expansive materials to the concrete. **(5 pp; 96:546)**

ART

Concrete Art Gets Noticed: Colorado artist uses concrete and custom-designed forms to produce award-winning flatwork, walls, and furniture. **(3 pp; 96:826)**

BRIDGES

Cable Stays Keep Bridge Formwork above Water: General contractor and construction engineer build cast-in-place spandrel arch ribs over the Presumpscot River in Falmouth, Maine, without using falsework. **(2 pp; 96:157)**

COLORED CONCRETE

Creating an Artistic Concrete Intersection: Installing a multicolored concrete intersection in Denver required use of integrally colored concrete, dry-shake hardeners, and stains. **(3 pp; 96:68)**

CONCRETE CANOES

Concrete Boats Afloat on Lake Mendota: Highlights of the ninth annual National Concrete Canoe Competition, organized by the American Society of Civil Engineers and Master Builders Inc. **(2 pp; 96:686)**

CONSOLIDATION

Choosing an Internal Vibrator: An overview of the different flexible-shaft and motor-in-head vibrators available to cast-in-place concrete contractors. **(5 pp; 96:399)**

CRACKING

Transverse Cracking in Recycled Concrete Aggregate Pavements: A Michigan Department of Transportation study finds that substituting recycled concrete aggregate for virgin gravel in standard structural-concrete mix designs may compromise pavement performance. **(5 pp; 96:570)**

CURING

Tips for Curing Cast-in-Place Architectural Concrete: Discusses what to consider when curing vertical or horizontal architectural concrete surfaces, since different finishes require different curing techniques. **(3 pp; 96:823)**

DESIGN

CRSI Names 1996 Design Award Winners: Project details for six cast-in-place reinforced concrete structures, the winners of this biennial design competition co-sponsored by the Concrete Reinforcing Steel Institute and the American Institute of Architects. **(5 pp; 96:352)**

Post-Tensioned Hybrid Slabs on Plastic Clay: A hybrid slab—a combination of a ribbed perimeter and a uniform-thickness interior—can be an economical alternative to ribbed post-tensioned slabs, especially in problem soil areas. **(2 pp; 96:619)**

FIBER REINFORCEMENT

Mixing, Placing, and Finishing Fiber-Reinforced Concrete: Tips for effectively mixing, placing, and finishing concrete reinforced with steel or synthetic fibers. **(3 pp; 96:537)**

FINISHING

Use the Right Finishing Tool at the Right Time: How to avoid common finishing mistakes, which can cause surface defects such as craze cracking, dusting, blistering, scaling, and random cracking. **(3 pp; 96:395)**

FLOORS

Using the F-Number System to Manage Floor Installations: Consultant tells how contractors can use F-numbers to control floor surface tolerances and manage the quality of concrete floor slab installations (Part 1 of 2). **(5 pp; 96:28)**

Using the F-Number System to Manage Floor Installations: Excerpts from a sample specification show how F-number requirements are typically addressed in project specifications for random-traffic floors (Part 2 of 2). **(3 pp; 96:176)**

A Look at Liquid Floor Hardeners: How liquid chemical treatments can be used on concrete to harden and densify weakened industrial floors. **(4 pp; 96:36)**

Flatness Tolerances for Random-Traffic Floors: Floor flatness can be measured using a number of different methods, including the ASTM E 1486-94 Waviness Index (Part 1 of 2). **(8 pp; 96:42)**

Using the Waviness Index to Improve Floor Flatness: Using the ASTM E 1486-94 Waviness Index to build flatter concrete floors (Part 2 of 2). **(5 pp; 96:359)**

Controlling Slab Curling: The slab on grade for a gymnasium floor at Elmira College was carefully designed and built to minimize curling problems. **(3 pp; 96:475)**

Troubleshooting Existing Floor Slabs: What investigators should

Annual Index of Articles 1996

ADMIXTURES

Using Admixtures to Improve Chemical Resistance of Concrete: What admixtures can and can't do to reduce concrete permeability and improve its resistance to leaching, sulfates, and acids. **(3 pp; 96:541)**

New Admixture Combats Concrete Shrinkage: A new liquid admixture allows contractors and ready mix producers to reduce shrinkage without adding expansive materials to the concrete. **(5 pp; 96:546)**

ART

Concrete Art Gets Noticed: Colorado artist uses concrete and custom-designed forms to produce award-winning flatwork, walls, and furniture. **(3 pp; 96:826)**

BRIDGES

Cable Stays Keep Bridge Formwork above Water: General contractor and construction engineer build cast-in-place spandrel arch ribs over the Presumpscot River in Falmouth, Maine, without using falsework. **(2 pp; 96:157)**

COLORED CONCRETE

Creating an Artistic Concrete Intersection: Installing a multicolored concrete intersection in Denver required use of integrally colored concrete, dry-shake hardeners, and stains. **(3 pp; 96:68)**

CONCRETE CANOES

Concrete Boats Afloat on Lake Mendota: Highlights of the ninth annual National Concrete Canoe Competition, organized by the American Society of Civil Engineers and Master Builders Inc. **(2 pp; 96:686)**

CONSOLIDATION

Choosing an Internal Vibrator: An overview of the different flexible-shaft and motor-in-head vibrators available to cast-in-place concrete contractors. **(5 pp; 96:399)**

CRACKING

Transverse Cracking in Recycled Concrete Aggregate Pavements: A Michigan Department of Transportation study finds that substituting recycled concrete aggregate for virgin gravel in standard structural-concrete mix designs may compromise pavement performance. **(5 pp; 96:570)**

CURING

Tips for Curing Cast-in-Place Architectural Concrete: Discusses what to consider when curing vertical or horizontal architectural concrete surfaces, since different finishes require different curing techniques. **(3 pp; 96:823)**

DESIGN

CRSI Names 1996 Design Award Winners: Project details for six cast-in-place reinforced concrete structures, the winners of this biennial design competition co-sponsored by the Concrete Reinforcing Steel Institute and the American Institute of Architects. **(5 pp; 96:352)**

Post-Tensioned Hybrid Slabs on Plastic Clay: A hybrid slab—a combination of a ribbed perimeter and a uniform-thickness interior—can be an economical alternative to ribbed post-tensioned slabs, especially in problem soil areas. **(2 pp; 96:619)**

FIBER REINFORCEMENT

Mixing, Placing, and Finishing Fiber-Reinforced Concrete: Tips for effectively mixing, placing, and finishing concrete reinforced with steel or synthetic fibers. **(3 pp; 96:537)**

FINISHING

Use the Right Finishing Tool at the Right Time: How to avoid common finishing mistakes, which can cause surface defects such as craze cracking, dusting, blistering, scaling, and random cracking. **(3 pp; 96:395)**

FLOORS

Using the F-Number System to Manage Floor Installations: Consultant tells how contractors can use F-numbers to control floor surface tolerances and manage the quality of concrete floor slab installations (Part 1 of 2). **(5 pp; 96:28)**

Using the F-Number System to Manage Floor Installations: Excerpts from a sample specification show how F-number requirements are typically addressed in project specifications for random-traffic floors (Part 2 of 2). **(3 pp; 96:176)**

A Look at Liquid Floor Hardeners: How liquid chemical treatments can be used on concrete to harden and densify weakened industrial floors. **(4 pp; 96:36)**

Flatness Tolerances for Random-Traffic Floors: Floor flatness can be measured using a number of different methods, including the ASTM E 1486-94 Waviness Index (Part 1 of 2). **(8 pp; 96:42)**

Using the Waviness Index to Improve Floor Flatness: Using the ASTM E 1486-94 Waviness Index to build flatter concrete floors (Part 2 of 2). **(5 pp; 96:359)**

Controlling Slab Curling: The slab on grade for a gymnasium floor at Elmira College was carefully designed and built to minimize curling problems. **(3 pp; 96:475)**

Troubleshooting Existing Floor Slabs: What investigators should

look for when they are called in to evaluate common floor problems. **(3 pp; 96:496)**

Plastic Sleeve Speeds Slip-Dowel Installation: A patented dowel system eliminates the need to drill forms for dowel placement, simplifying the placement of steel slip dowels at construction joints. **(4 pp; 96:867)**

FORMING

Choosing and Using a Form Release Agent: How to select the best barrier or chemically active release agent for nonporous, semiporous, and porous form materials. **(4 pp; 96:732)**

Raker-Beam Construction Requires Rugged Steel Forms: Construction of a San Diego State University arena requires contractor to assemble rebar cages on the ground, lift each cage onto columns, and enclose it within a 55,000-pound self-spanning steel form. **(4 pp; 96:738)**

Selecting Form Ties: An overview of different form-tie types (one or three piece), load capacities, tie-hole patching requirements, and safety factors. **(3 pp; 96:771)**

What Is a Smooth Form Finish?: The new requirements for a smooth form finish, as defined by the American Concrete Institute's *Standard Specifications for Structural Concrete* (ACI 301-96). **(2 pp; 96:817)**

FORMWORK

Meeting Special Design Needs with Custom Wood Forms: Advantages of using custom wood forms to produce complex transitions, tight radii, or architectural shapes. **(5 pp; 96:333)**

Architectural Details Enhance a Texas Overpass: Steel and wood forms are combined to create a functional yet decorative bridge: the Liberty-Laurel Overpass in Beaumont, Texas. **(4 pp; 96:748)**

An Aluminum 2x4?: An extruded aluminum beam offers higher load-carrying capacity and longer service life than comparable wood supports and can readily be used to support job-built forms. **(4 pp; 96:871)**

Tips for Placing Concrete into Insulating Wall Forms: Steps for successfully placing concrete into insulating concrete forms, including conducting a prepour inspection, ordering the right concrete mix, choosing the right placing equipment, and using the correct pour pattern. **(4 pp; 96:925)**

HISTORY

St. Francis de Sales Church: The close collaboration in the mid-1960s between architect and concrete contractor results in a striking cast-in-place concrete structure: St. Francis de Sales Church, Muskegon, Mich. **(4 pp; 96:561)**

S.C. Johnson & Son Complex Symbolizes Concrete's Versatility and Endurance: The planning and construction of this Racine, Wis.-based company's headquarters, designed by Frank Lloyd Wright more than 55 years ago. **(4 pp; 96:675)**

JOINTS

How to Stop Cheating on Industrial-Floor Joint Filling: Ways to identify and discourage cheating on industrial-floor joint filling and the consequences of improperly filled joints. **(5 pp; 96:469)**

LANDSCAPING

Selling Homeowners on Concrete Landscaping: Marketing cast-in-place concrete as a residential landscaping material starts by acquainting homeowners with concrete's versatility, durability, and economy. **(3 pp; 96:604)**

LASERS

Buying a Laser Leveling System: An overview of the capabilities and costs of visible- and invisible-beam lasers as well as what features concrete contractors should look for. **(6 pp; 96:412)**

MANAGEMENT

Choosing Construction Estimating Software: The top 10 questions contractors need to ask to assess different estimating programs and choose the one that can best streamline takeoffs and improve bid accuracy. **(4 pp; 96:56)**

Dear Customer: You're Fired: How to analyze whether it's worthwhile to end a business relationship with a customer or client by assessing business practices, behavior, and payment history. **(2 pp; 96:72)**

15 Easy Ways to Kill Work Force Productivity: Fifteen practices managers should avoid—unless they want to kill worker productivity and weaken business. **(2 pp; 96:428)**

Renting, Leasing, or Owning Construction Equipment: Deciding which option is best requires contractors to carefully evaluate their financial positions. **(3 pp; 96:499)**

Management Information eXchange Groups: A new program organized by the American Society for Concrete Construction encourages noncompeting contractors to gather in small groups to discuss business practices and share technical information. **(3 pp; 96:682)**

Developing and Motivating Employees: Finding the right people, evaluating worker satisfaction, and applying a variety of motivational strategies can lead to improved customer satisfaction and increased profits. **(2 pp; 96:830)**

Rising Above the Competition: Effective ways contractors can differentiate their businesses, since it takes more than a low bid to win a job. **(3 pp; 96:834)**

MATERIAL HANDLING

Air Pump Increases Material-Handling Options: A pneumatic pump transports and places granular base material over rough terrain or in confined areas. **(2 pp; 96:246)**

High-Volume Pumping Places Large Slabs Monolithically: Despite tough site constraints, construction team achieves placement rates of up to 300 cubic yards per hour for the floor and roof slabs of a 208-foot-diameter, 30-foot-tall concrete clearwell in Westminster, Colo. **(2 pp; 96:665)**

Slipformed Grade Beams Speed Foundation Construction: Slipforming more than 5,000 lineal feet of grade beam for the structural slab of a recreational facility in Sault Ste. Marie, Mich., saves concrete contractor time and money. **(3 pp; 96:668)**

Side-Discharge Conveyor Places More Than 20 Truckloads of Concrete an Hour: To construct the people-mover tunnels at Hong

Kong's new Chek Lap Kok Airport, contractor relies on a side-discharge conveyor that places more than 160 cubic yards of concrete per hour. **(2 pp; 96:672)**

METRICS

Practical Metrication in the Concrete Industry: A proposed table of rational metric-conversion values that industry personnel can use when specifying, ordering, and testing concrete. **(2 pp; 96:931)**

NOTABLE PROJECTS

Las Vegas Bites into the Big Apple: How a design team, managing contractor, and concrete pumper worked together to construct Las Vegas' New York-New York Hotel & Casino, a multiheight high-rise that represents the best of the Big Apple. **(6 pp; 96:15)**

Concrete Super Bowl '95: General contractor takes only 31 days to place 600,108 square feet of concrete slabs for a new training center at the Pensacola Naval Air Station. **(3 pp; 96:182)**

Concrete Runway Built for Smooth Landings: Paving contractor uses specialized paving equipment—a four-track slipform paver, a custom-built belt placer, and a rubber-tired material transfer/placer—to place a 150-foot-wide, 17-inch-thick runway at Dallas/Fort Worth International Airport. **(4 pp; 96:259)**

Double the Weight, Double the Challenges: Building a linear accelerator facility in Pontiac, Mich., using a 300-pcf concrete mix requires concrete contractor to overcome unique problems related to the heavyweight concrete mix, including efficient material delivery and proper concrete placement. **(6 pp; 96:421)**

Concrete Changes the Face of Theodore Roosevelt Dam: Contractor works with the U.S. Bureau of Reclamation to restore Arizona's historic masonry dam, using an overlay of mass concrete blocks to raise the dam's height 77 feet and increase its water conservation storage capacity 20%. **(5 pp; 96:505)**

PATTERN STAMPING

The 7 Deadly Sins of Pattern Stamping: The seven most common errors that occur in pattern-stamped flatwork and how contractors can avoid them. **(3 pp; 96:811)**

PAVING

Fixed-Form Paving: A Lost Art: How to obtain good results when using fixed paving forms, because there are still many applications, including streets, intersections, and variable-width pavements, where fixed paving forms are more practical and cost effective than slipform pavers. **(4 pp; 96:62)**

Tips for Reconstructing Concrete Intersections: How to meet specifications and minimize traffic disruptions while constructing concrete intersections, which present contractors with special challenges. **(4 pp; 96:160)**

Slipform Paver Rises to the Occasion: To build the International Horse Park, a multimillion-dollar facility in Conyers, Ga., contractor uses a three-track paver equipped with a special mold that allows for the slipforming of 22 rows of risers in two weeks. **(2 pp; 96:179)**

Tackling Tight Turns: How to best assess job logistics, prepare subgrade, set stringline and radius wheels, and operate curb-and-gutter machines when slipforming curbs with a radius of less than 10 feet. **(4 pp; 96:240)**

1996 ACPA Awards Spotlight People, Products, and Paving Materials: A profile of the winners and runners-up in the seventh annual National Awards Program for Excellence in Concrete Pavement, sponsored by the American Concrete Pavement Association and *Concrete Construction.* **(5 pp; 96:935)**

POST-TENSIONING

Concrete Handles the Pressure: An experiment at Brooks Air Force Base indicates that post-tensioned concrete can be a cost-effective alternative to steel when constructing the specialized chambers where hyperbaric oxygen treatments are administered. **(3 pp; 96:847)**

PROBLEM CLINIC

January (8 pp; 96:76)

- Readers' Solutions to Dark Patches on Tilt-Up Panels
- Can Changes in Fine Aggregate Affect Concrete Finishability?
- Can Concrete Be Rejected after One Slump Test?

February (3 pp; 96:187)

- Preventing Lignite from Floating to Slab Surfaces
- Methods for Determining In-Place Flexural Strength
- Permissible Levels of Chlorides and Sulfates in Aggregate

March (1 p; 96:278)

- Can Rebound Hammer Results Determine Safe Form-Stripping Time?
- Stay-in-Place Divider Strips and Side Forms for Flatwork

April (2 pp; 96:364)

- Fine, White Powder on Concrete Surface
- Permeability of Air-Entrained Concrete
- Shelf Life for Portland Cement
- Correction: Flexural Strength/Compressive Strength Relationship

May (2 pp; 96:434)

- More on Permissible Levels of Chlorides and Sulfates
- Tolerance on Top-of-Wall Elevation

June (2 pp; 96:510)

- Cause of a Dusting Floor
- More on Permeability of Air-Entrained Concrete

July (2 pp; 96:576)

- Removing Excess Bond Breaker from Tilt-Up Panels
- How Often Should Fresh Concrete Be Tested?

August (2 pp; 96:630)

- Make Sure Construction Joints Line Up
- Clear Sealer Peels Off
- Isolation Joint Depth
- What Is Type I-II Cement?
- Standard Method for Detecting Delaminated Concrete?

September (3 pp; 96:688)

- Circular Cracks around Columns
- Does Water Content Affect Setting Time?
- Can You Broom Texture a Hard-Troweled Surface?
- D-Cracking vs. ASR-Cracking
- Avoiding Scaling and Sheet Scaling

- Effect of Absorbed Water on Water-Cement Ratio

October (1 p; 96:774)
- Causes for Slab Discoloration
- How to Splice PVC Waterstops
- Effect of Hard Water on Concrete

November (3 pp; 96:875)
- More on Joints
- Causes of Sealer Delamination
- More on the Cause of a Dusting Floor
- Finishing Lightweight Concrete on Elevated Decks

December (1 p; 96:945)
- Pinwheel Joints
- Durable Concrete for Ice Skating Rink
- Best Coating for Embedded Aluminum Conduit

PRODUCT PROFILE

Hydraulic Rams Put Curves in Legs of Stratosphere Tower: Six 150-ton hydraulic rams help contractor produce camber in the three 20x32-foot rectangular concrete legs of this 1,149-foot-tall tower in Las Vegas. **(3 pp; 96:131)**

Polyurethane Coating System Deters Graffiti Artists: A polyurethane coating system seals concrete, improves its appearance, and eases removal of spray paint and other graffiti. **(1 p; 96:209)**

Unique Mold Speeds Slipforming of Cattle Troughs: A multipurpose paver equipped with a special mold allows contractor to slipform a cattle trough and adjacent pad in one pass. **(1 p; 96:585)**

PUMPING

Tips for Profitably Using Small-Line Pumps: How to use small-line equipment, which can be used profitably on small-volume pours and even on larger pours requiring slow placing rates. **(4 pp; 96:406)**

REINFORCEMENT

Distributed Steel for Concrete Floors: What's the Right Amount?: Better control of steel position and less likelihood of unacceptably wide cracks are just two of the reasons for using greater amounts of reinforcing steel than called for by traditional subgrade-drag theory. **(6 pp; 96:487)**

RESIDENTIAL CONSTRUCTION

Building a Concrete Dome House: A former mechanic uses a kit and site-mixed concrete to construct his own retirement home—a 30-foot-wide, 15-foot-tall geodesic dome with 1,060 square feet of living area. **(3 pp; 96:266)**

Home Remodeled with Concrete: A builder's use of expanded polystyrene forms to erect an energy-efficient home addition in southeast Michigan. **(4 pp; 96:608)**

SHORING

Design Guidelines for Formwork Shoring Towers: A summary of shoring towers' components, safe working loads, and general layout guidelines, since various systems can support formwork for a wide range of applications. **(4 pp; 96:743)**

SHOTCRETE

Be Sure to Cure a Shotcrete Pool: To build long-lasting in-ground swimming pools, a former pool builder turned troubleshooter emphasizes the importance of promptly curing the shotcrete and protecting it during hot or cold weather. **(3 pp; 96:614)**

SOIL COMPACTION

Compacting Soils and Subbases: Contractors should evaluate soil type, moisture content, and field-test results to pick the right compaction equipment for the job. **(4 pp; 96:233)**

SPECIFICATIONS

Using the New ACI 301: How the American Concrete Institute's ACI 301-96, *Standard Specifications for Structural Concrete,* differs from its predecessor, ACI 301-89, *Specifications for Structural Concrete for Buildings.* **(5 pp; 96:340)**

TESTING

Slab Moisture Testing: Is It Always Reliable?: Case study illustrates how environmental and construction factors can affect moisture-emission test results for slabs that will be covered by impermeable toppings. **(4 pp; 96:480)**

Fast Field Tests for Concrete: Applications for various nondestructive testing devices that can be used on-site to quickly measure water-cement ratio, chloride or alkali content, and fresh-concrete consistency. **(6 pp; 96:552)**

TILT-UP

1996 Tilt-Up Achievement Awards: Project details for the nine winners of this annual competition, sponsored by the Tilt-Up Concrete Association. **(3 pp; 96:348)**

TOLERANCES

Tolerance Conflicts in Concrete Construction: Since structures can vary from planned line and dimension yet still be considered in contract compliance, contractors, architect-engineers, and owners should plan ahead to reduce the likelihood of conflicting tolerances. **(7 pp; 96:621)**

TROUBLESHOOTING

Solutions to Scaling Concrete: How to determine the causes of light, medium, severe, or very severe scaling and the importance of ensuring adequate air entrainment, finishing, curing, and strength development to produce durable concrete pavements. **(5 pp; 96:250)**

TUNNEL CONSTRUCTION

Lining the Calumet Tunnel: Construction team achieves record-setting tunneling and concrete-lining rates as it completes an 11.6-mile flood-control tunnel in suburban Chicago well ahead of schedule. **(3 pp; 96:165)**

WATERSTOPS

Stop Water in Its Tracks: An overview of the selection, installation, and features of strip-applied waterstops, which perform best in contained environments, under constant compression. **(4 pp; 96:169)**

WHITETOPPING

Ultra-Thin Whitetopping Smooths Highway Intersection: How the Pennsylvania Department of Transportation successfully completed its first ultra-thin whitetopping project, a fast-track overlay of a rutted asphalt intersection in Lancaster, Pa. **(4 pp; 96:430)**